



Engineering
& Design

Stormwater Management Report


October 18, 2024

Proposed Residential Improvements
Block 106, Lot 24.01
Town of West Orange, Essex County, New Jersey

Prepared for:

The Waymaker, LLC
40 Eagle Ridge Way
West Orange, NJ 07052

Prepared by:


Jesse B. Cokeley, P.E.
New Jersey Professional Engineer
License No. GE54006

Colliers Engineering & Design

300 Tice Boulevard Suite 101
Woodcliff Lake, NJ 07677
Main: 877 627 3772
Colliersengineering.com

Project No. 24006174A

Table of Contents

Limitation.....	1
Introduction.....	2
Purpose	2
Method.....	2
Stormwater Quantity	3
1.1 Stormwater Management.....	3
1.2 Summary Table.....	3
1.3 Stormwater Management Facility Operations and Maintenance.....	3
1.4 Conveyance System.....	3
Stormwater Quality	4
Groundwater Recharge (N.J.A.C. 7:8-5.4).....	4
Groundwater Recharge Summary	4
Conclusion	4
Appendix A	
HydroCAD Output	
Appendix B	
Recharge Worksheet	
Appendix C	
Existing and Proposed Drainage Area Map	
Appendix D	
USGS	
HUC-11	
Soil Survey Location Map	
Appendix E - Not Included in this Submission	
Low Impact Development	
Appendix F - Not Included in this Submission	
Stormwater Conveyance System	

Limitation

The sole purpose of this report and the associated services performed by Colliers Engineering & Design, Inc., is to undertake a hydrologic assessment for the proposed residential development in accordance with the scope of services set out in the contract between Colliers Engineering & Design and The Waymaker, LLC.

Colliers Engineering & Design derived the data in this report from a variety of sources. The sources are identified at the time or times outlined in this report. The passage of time, manifestation of latent conditions or impacts of future events may require further examination of the project and subsequent data analysis, and re-evaluation of the data, findings, observations, and conclusions expressed in this report. Colliers Engineering & Design has prepared this report in accordance with the usual care and thoroughness of the consulting profession, for the sole purpose of the project and by reference to applicable standards, procedures, and practices at the date of issue of this report. For the reasons outlined above, however, no other warranty or guarantee, whether expressed or implied, is made as to the data, observations and findings expressed in this report.

This report should be read in full, and no excerpts are to be taken as representative of the findings. No responsibility is accepted by Colliers Engineering & Design for use of any part of this report in any other context.

This report has been prepared on behalf of, and for the exclusive use of The Waymaker, LLC and is subject to, and issued in connection with, the provisions of the agreement between Colliers Engineering & Design and The Waymaker, LLC.

Introduction

This Stormwater Management Report for the proposed project has been prepared by Colliers Engineering & Design for The Waymaker, LLC. Colliers Engineering & Design performed a hydrological assessment for the property located at 42 Eagle Ridge Way, West Orange, New Jersey, also defined as Block 106, Lot 24.01. The site is currently ± 3.09 -acres in size and was previously occupied by a single-family home and associated driveways and site improvements. The house was recently demolished and the property was cleared, and is currently occupied by stockpiles of gravel and other materials. The proposed development consists of the construction of a single-family home and a barn and indoor arena for the keeping of horses. There will also be an outdoor arena, grass paddocks, and associated driveways and pathways. The proposed development results in a total disturbance of approximately 3.13 acres and a total impervious area of approximately 0.40 acres (0.19-acre increase) within the proposed development area.

Purpose

This report assesses the hydrologic aspects, and the stormwater drainage conditions as a result of the proposed construction, including the house, barn, arenas, paddocks, landscaping areas, stormwater management facilities, associated utilities, and related site improvements.

The focus of the study is the identification of the existing drainage characteristics prior to the demolition of the house in comparison to post-development conditions. Calculations documenting the design of the stormwater management system are illustrated on the Site Plan drawing documents, prepared by Colliers Engineering & Design.

Method

Generally, stormwater runoff from the site flows overland from west to east and discharges to an existing drainage channel located at the northeastern corner of the site (Design Point 1). The remainder of the site drains overland to the south (Design Point 2). The area, curve number, and time of concentration for each existing watershed can be seen on the Existing Drainage Area Map included in the appendix. For the purposes of this analysis the existing conditions include the previously demolished house and site improvements.

Under proposed conditions, the site will generally mimic the existing drainage pattern; however, the majority of the proposed development will be captured and routed through subsurface infiltration basins to attenuate peak flows. New inlets and pipes will be installed to convey the stormwater runoff from certain areas to the infiltration basins. Tributary areas to the infiltration basins are outlined on the Proposed Drainage Area Map and include the house, barn, arenas, and the majority of the proposed pathways and paddocks. The area, curve number, and time of concentration for each proposed watershed can be found on the Proposed Drainage Area Map and HydroCAD output included in the appendix.

Stormwater Quantity

1.1 Stormwater Management

As mentioned above, a subsurface infiltration basin has been designed to provide water quantity mitigation for the runoff discharging to the existing drainage channel. As the site is located in HSG 'C' soils, infiltration is anticipated to be the minimum allowable 1 in/hr. Soil testing, including groundwater elevation determination, will be performed prior to construction. Full HydroCAD output calculations are provided in the appendix. The results are summarized in the table below.

1.2 Summary Table

<i>Description</i>	<i>2 Year Storm</i>	<i>10 Year Storm</i>	<i>100 Year Storm</i>
A. Existing Conditions			
Design Point 1	2.85 cfs	5.99 cfs	12.64 cfs
Required Reductions (50%, 75%, 80%)	1.43 cfs	4.49 cfs	10.11 cfs
Design Point 2	0.55 cfs	1.19 cfs	2.54 cfs
Required Reductions (50%, 75%, 80%)	0.28 cfs	0.89 cfs	2.03 cfs
B. Proposed Conditions			
Design Point 1	1.41 cfs	4.41 cfs	9.24 cfs
Design Point 2	0.26 cfs	0.55 cfs	1.14 cfs

According to §25-29.4.r of the Township of West Orange, stormwater management measures shall be designed so that the post-construction peak runoff rates for the 2-, 10-, and 100-year storm events are 50%, 75%, and 80%, respectively, of the preconstruction peak runoff rates. As can be seen in the Summary Table above, the post-construction peak runoff rates for the 2-, 10-, and 100-year storm events have been reduced below the required peak runoff rates.

1.3 Stormwater Management Facility Operations and Maintenance

The long-term operations and maintenance of the proposed stormwater management facilities shall be performed in accordance with the Stormwater Management Facility Operations & Maintenance Manual prepared by Colliers Engineering & Design (under separate cover). This Manual explains how often maintenance should be performed and how long it should take for the proposed on-site stormwater management systems (porous pavement) to drain to ensure proper operation. Tables showing the data to support the listed drain times are included in the appendix of this report.

1.4 Conveyance System

Pipe sizing calculations will be provided prior to final approval. Pipe sizing calculations will be performed using the Rational Method and 25-year design storm for capacity verification.

Stormwater Quality

As per NJDEP Regulations, stormwater management measures shall only be required for water quality control if an additional $\frac{1}{4}$ acre of regulated motor vehicle surface is being proposed on a development site. For this project, the existing motor vehicle surface area totals approximately 0.19 acres and the proposed motor vehicle surface area totals approximately 0.40 acres, which results in a increase of 0.21 acres. Therefore, as the proposed improvements result in less than $\frac{1}{4}$ acre of new regulated motor vehicle surfaces, water quality treatment is not required.

Groundwater Recharge (N.J.A.C. 7:8-5.4)

To meet Township and NJDEP requirements for groundwater recharge, the proposed development is designed to maintain 100 percent of the average annual pre-construction groundwater recharge volume for the site. As the entire subject property falls within one (1) HUC-14 sub-watershed, compliance with the groundwater recharge standard is met by analyzing the site as a whole. The site is within the Passaic River Lower (Nwk Bay to Saddle) HUC-14 drainage area.

The New Jersey Groundwater Recharge Spreadsheet, Version 2.0, November 2003 is utilized to calculate the post-development annual recharge deficit for the project site and annual recharge volume for each proposed BMP. The following table provides a summary of the post-development deficit and proposed recharge volume. Full calculation spreadsheets and a summary of the proposed recharge volume for each BMP are provided in the Appendix.

Groundwater Recharge Summary

HUC-14 Drainage Area	Pre-Development Total Annual Recharge (cubic feet)	Proposed Annual Recharge Volume (cubic feet)	Percentage of Average Annual Pre-Construction Groundwater Recharge Volume
Passaic River Lower (Nwk Bay to Saddle)	150,467	170,368	113.23%




As shown in the above table, the proposed development is designed to maintain 100 percent of the average annual pre-construction groundwater recharge volume for the site.

Conclusion

As discussed above, water quantity mitigation is provided for all watersheds for all storm events studied in accordance with NJDEP and Township of West Orange regulations. A subsurface infiltration basin was utilized to achieve the required reductions for all Design Points. Furthermore, water quality treatment is not required for this project site. As such, there should be no adverse impacts due to stormwater, on-site or off-site, as a result of the proposed development. Included in the appendix of this report is the HydroCAD output for back-up on both the existing and proposed conditions. Additionally, the aforementioned Existing and Proposed Drainage Area Maps, an Inlet Area Map and a Pipe Capacity Report are provided in the appendix of this report.

Appendix A

HydroCAD Output



Routing Diagram for 240924_42 ERW Waymaker
Prepared by Colliers Engineering & Design, Printed 10/17/2024
HydroCAD® 10.20-4b s/n 04431 © 2023 HydroCAD Software Solutions LLC

Project Notes

Rainfall events imported from "NRCS2-Rain.txt" for 1167 NJ Essex-D

Rainfall Events Listing (selected events)

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Year	NOAA 24-hr	D	Default	24.00	1	3.44	2
2	10-Year	NOAA 24-hr	D	Default	24.00	1	5.22	2
3	100-Year	NOAA 24-hr	D	Default	24.00	1	8.66	2
4	WQ	NJ DEP 2-hr		Default	2.00	1	1.25	2

Area Listing (selected nodes)

Area (acres)	CN	Description (subcatchment-numbers)
2.773	74	>75% Grass cover, Good, HSG C (EDA-1 (PERV), EDA-2 (PERV.))
0.319	98	Paved parking, HSG C (EDA-1 (IMPERV))
3.092	76	TOTAL AREA

Soil Listing (selected nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
3.092	HSG C	EDA-1 (IMPERV), EDA-1 (PERV), EDA-2 (PERV.)
0.000	HSG D	
0.000	Other	
3.092		TOTAL AREA

240924_42 ERW Waymaker

Prepared by Colliers Engineering & Design

HydroCAD® 10.20-4b s/n 04431 © 2023 HydroCAD Software Solutions LLC

Printed 10/17/2024

Page 6

Ground Covers (selected nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	2.773	0.000	0.000	2.773	>75% Grass cover, Good	EDA-1 (PERV), EDA-2 (PERV.)
0.000	0.000	0.319	0.000	0.000	0.319	Paved parking	EDA-1 (IMPERV)
0.000	0.000	3.092	0.000	0.000	3.092	TOTAL AREA	

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EDA-1 (IMPERV): Runoff Area=13,913 sf 100.00% Impervious Runoff Depth=3.21"
Flow Length=275' Tc=2.8 min CN=98 Runoff=1.14 cfs 0.085 af

Subcatchment EDA-1 (PERV): Runoff Area=102,351 sf 0.00% Impervious Runoff Depth=1.20"
Flow Length=501' Tc=13.1 min CN=74 Runoff=2.46 cfs 0.235 af

Subcatchment EDA-2 (PERV.): Runoff Area=18,430 sf 0.00% Impervious Runoff Depth=1.20"
Flow Length=121' Tc=7.2 min CN=74 Runoff=0.55 cfs 0.042 af

Reach DP1-EX: Inflow=2.85 cfs 0.320 af
Outflow=2.85 cfs 0.320 af

Reach DP2-EX: Inflow=0.55 cfs 0.042 af
Outflow=0.55 cfs 0.042 af

Total Runoff Area = 3.092 ac Runoff Volume = 0.362 af Average Runoff Depth = 1.41"
89.67% Pervious = 2.773 ac 10.33% Impervious = 0.319 ac


Summary for Subcatchment EDA-1 (IMPERV):[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 1.14 cfs @ 12.09 hrs, Volume= 0.085 af, Depth= 3.21"
 Routed to Reach DP1-EX :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 2-Year Rainfall=3.44"

Area (sf)	CN	Description
13,913	98	Paved parking, HSG C
13,913		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	78	0.0150	1.21		Sheet Flow, Smooth surfaces $n=0.011$ $P2=3.44"$
1.0	12	0.0800	0.20		Sheet Flow, Grass: Short $n=0.150$ $P2=3.44"$
0.7	185	0.0830	4.64		Shallow Concentrated Flow, Unpaved $K_v=16.1$ fps
2.8	275	Total			

Subcatchment EDA-1 (IMPERV):


Summary for Subcatchment EDA-1 (PERV):

Runoff = 2.46 cfs @ 12.22 hrs, Volume= 0.235 af, Depth= 1.20"
 Routed to Reach DP1-EX :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 2-Year Rainfall=3.44"

Area (sf)	CN	Description
102,351	74	>75% Grass cover, Good, HSG C
102,351		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.9	100	0.0140	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
2.2	401	0.0350	3.01		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
13.1	501	Total			

Subcatchment EDA-1 (PERV):

Summary for Subcatchment EDA-2 (PERV.):

Runoff = 0.55 cfs @ 12.15 hrs, Volume= 0.042 af, Depth= 1.20"
 Routed to Reach DP2-EX :


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 2-Year Rainfall=3.44"

Area (sf)	CN	Description
18,430	74	>75% Grass cover, Good, HSG C
18,430		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.1	100	0.0410	0.24		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.1	21	0.1050	5.22		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.2	121	Total			

Subcatchment EDA-2 (PERV.):

Hydrograph




Summary for Reach DP1-EX:

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.669 ac, 11.97% Impervious, Inflow Depth = 1.44" for 2-Year event
Inflow = 2.85 cfs @ 12.20 hrs, Volume= 0.320 af
Outflow = 2.85 cfs @ 12.20 hrs, Volume= 0.320 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Reach DP1-EX:**Hydrograph**

Summary for Reach DP2-EX:

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.423 ac, 0.00% Impervious, Inflow Depth = 1.20" for 2-Year event
Inflow = 0.55 cfs @ 12.15 hrs, Volume= 0.042 af
Outflow = 0.55 cfs @ 12.15 hrs, Volume= 0.042 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP2-EX:**Hydrograph**

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EDA-1 (IMPERV):Runoff Area=13,913 sf 100.00% Impervious Runoff Depth=4.98"
Flow Length=275' Tc=2.8 min CN=98 Runoff=1.74 cfs 0.133 af**Subcatchment EDA-1 (PERV):**Runoff Area=102,351 sf 0.00% Impervious Runoff Depth=2.54"
Flow Length=501' Tc=13.1 min CN=74 Runoff=5.39 cfs 0.498 af**Subcatchment EDA-2 (PERV.):**Runoff Area=18,430 sf 0.00% Impervious Runoff Depth=2.54"
Flow Length=121' Tc=7.2 min CN=74 Runoff=1.19 cfs 0.090 af**Reach DP1-EX:**Inflow=5.99 cfs 0.630 af
Outflow=5.99 cfs 0.630 af**Reach DP2-EX:**Inflow=1.19 cfs 0.090 af
Outflow=1.19 cfs 0.090 af**Total Runoff Area = 3.092 ac Runoff Volume = 0.720 af Average Runoff Depth = 2.79"**
89.67% Pervious = 2.773 ac 10.33% Impervious = 0.319 ac


Summary for Subcatchment EDA-1 (IMPERV):[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 1.74 cfs @ 12.09 hrs, Volume= 0.133 af, Depth= 4.98"
 Routed to Reach DP1-EX :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 10-Year Rainfall=5.22"

Area (sf)	CN	Description
13,913	98	Paved parking, HSG C
13,913		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	78	0.0150	1.21		Sheet Flow, Smooth surfaces $n=0.011$ $P2=3.44"$
1.0	12	0.0800	0.20		Sheet Flow, Grass: Short $n=0.150$ $P2=3.44"$
0.7	185	0.0830	4.64		Shallow Concentrated Flow, Unpaved $K_v=16.1$ fps
2.8	275	Total			

Subcatchment EDA-1 (IMPERV):

Summary for Subcatchment EDA-1 (PERV):

Runoff = 5.39 cfs @ 12.21 hrs, Volume= 0.498 af, Depth= 2.54"
 Routed to Reach DP1-EX :


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 10-Year Rainfall=5.22"

Area (sf)	CN	Description
102,351	74	>75% Grass cover, Good, HSG C
102,351		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.9	100	0.0140	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
2.2	401	0.0350	3.01		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
13.1	501	Total			

Subcatchment EDA-1 (PERV):

Hydrograph




Summary for Subcatchment EDA-2 (PERV.):

Runoff = 1.19 cfs @ 12.15 hrs, Volume= 0.090 af, Depth= 2.54"
 Routed to Reach DP2-EX :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 10-Year Rainfall=5.22"

Area (sf)	CN	Description
18,430	74	>75% Grass cover, Good, HSG C
18,430		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.1	100	0.0410	0.24		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.1	21	0.1050	5.22		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.2	121	Total			


Subcatchment EDA-2 (PERV.):

Summary for Reach DP1-EX:

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.669 ac, 11.97% Impervious, Inflow Depth = 2.83" for 10-Year event
Inflow = 5.99 cfs @ 12.20 hrs, Volume= 0.630 af
Outflow = 5.99 cfs @ 12.20 hrs, Volume= 0.630 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Reach DP1-EX:**Hydrograph**

Summary for Reach DP2-EX:

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.423 ac, 0.00% Impervious, Inflow Depth = 2.54" for 10-Year event
Inflow = 1.19 cfs @ 12.15 hrs, Volume= 0.090 af
Outflow = 1.19 cfs @ 12.15 hrs, Volume= 0.090 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP2-EX:**Hydrograph**

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EDA-1 (IMPERV): Runoff Area=13,913 sf 100.00% Impervious Runoff Depth=8.42"
Flow Length=275' Tc=2.8 min CN=98 Runoff=2.89 cfs 0.224 af

Subcatchment EDA-1 (PERV): Runoff Area=102,351 sf 0.00% Impervious Runoff Depth=5.52"
Flow Length=501' Tc=13.1 min CN=74 Runoff=11.62 cfs 1.081 af

Subcatchment EDA-2 (PERV.): Runoff Area=18,430 sf 0.00% Impervious Runoff Depth=5.52"
Flow Length=121' Tc=7.2 min CN=74 Runoff=2.54 cfs 0.195 af

Reach DP1-EX: Inflow=12.64 cfs 1.305 af
Outflow=12.64 cfs 1.305 af

Reach DP2-EX: Inflow=2.54 cfs 0.195 af
Outflow=2.54 cfs 0.195 af

Total Runoff Area = 3.092 ac Runoff Volume = 1.500 af Average Runoff Depth = 5.82"
89.67% Pervious = 2.773 ac 10.33% Impervious = 0.319 ac


Summary for Subcatchment EDA-1 (IMPERV):[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 2.89 cfs @ 12.09 hrs, Volume= 0.224 af, Depth= 8.42"
 Routed to Reach DP1-EX :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 100-Year Rainfall=8.66"

Area (sf)	CN	Description
13,913	98	Paved parking, HSG C
13,913		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	78	0.0150	1.21		Sheet Flow, Smooth surfaces $n=0.011$ $P2=3.44"$
1.0	12	0.0800	0.20		Sheet Flow, Grass: Short $n=0.150$ $P2=3.44"$
0.7	185	0.0830	4.64		Shallow Concentrated Flow, Unpaved $K_v=16.1$ fps
2.8	275	Total			

Subcatchment EDA-1 (IMPERV):


Summary for Subcatchment EDA-1 (PERV):

Runoff = 11.62 cfs @ 12.21 hrs, Volume= 1.081 af, Depth= 5.52"
 Routed to Reach DP1-EX :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 100-Year Rainfall=8.66"

Area (sf)	CN	Description
102,351	74	>75% Grass cover, Good, HSG C
102,351		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.9	100	0.0140	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
2.2	401	0.0350	3.01		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
13.1	501	Total			

Subcatchment EDA-1 (PERV):


Summary for Subcatchment EDA-2 (PERV.):

Runoff = 2.54 cfs @ 12.14 hrs, Volume= 0.195 af, Depth= 5.52"
 Routed to Reach DP2-EX :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 100-Year Rainfall=8.66"

Area (sf)	CN	Description
18,430	74	>75% Grass cover, Good, HSG C
18,430		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.1	100	0.0410	0.24		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.1	21	0.1050	5.22		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.2	121	Total			


Subcatchment EDA-2 (PERV.):

Summary for Reach DP1-EX:

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.669 ac, 11.97% Impervious, Inflow Depth = 5.87" for 100-Year event
Inflow = 12.64 cfs @ 12.20 hrs, Volume= 1.305 af
Outflow = 12.64 cfs @ 12.20 hrs, Volume= 1.305 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Reach DP1-EX:**Hydrograph**

Summary for Reach DP2-EX:

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.423 ac, 0.00% Impervious, Inflow Depth = 5.52" for 100-Year event
Inflow = 2.54 cfs @ 12.14 hrs, Volume= 0.195 af
Outflow = 2.54 cfs @ 12.14 hrs, Volume= 0.195 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP2-EX:**Hydrograph**

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EDA-1 (IMPERV):Runoff Area=13,913 sf 100.00% Impervious Runoff Depth=1.03"
Flow Length=275' Tc=2.8 min CN=98 Runoff=0.96 cfs 0.028 af**Subcatchment EDA-1 (PERV):**Runoff Area=102,351 sf 0.00% Impervious Runoff Depth=0.07"
Flow Length=501' Tc=13.1 min CN=74 Runoff=0.28 cfs 0.014 af**Subcatchment EDA-2 (PERV.):**Runoff Area=18,430 sf 0.00% Impervious Runoff Depth=0.07"
Flow Length=121' Tc=7.2 min CN=74 Runoff=0.06 cfs 0.003 af**Reach DP1-EX:**Inflow=0.96 cfs 0.042 af
Outflow=0.96 cfs 0.042 af**Reach DP2-EX:**Inflow=0.06 cfs 0.003 af
Outflow=0.06 cfs 0.003 af**Total Runoff Area = 3.092 ac Runoff Volume = 0.045 af Average Runoff Depth = 0.17"**
89.67% Pervious = 2.773 ac 10.33% Impervious = 0.319 ac


Summary for Subcatchment EDA-1 (IMPERV):[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 0.96 cfs @ 1.05 hrs, Volume= 0.028 af, Depth= 1.03"
 Routed to Reach DP1-EX :

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NJ DEP 2-hr WQ Rainfall=1.25"

Area (sf)	CN	Description
13,913	98	Paved parking, HSG C
13,913		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.1	78	0.0150	1.21		Sheet Flow, Smooth surfaces $n=0.011$ $P2=3.44"$
1.0	12	0.0800	0.20		Sheet Flow, Grass: Short $n=0.150$ $P2=3.44"$
0.7	185	0.0830	4.64		Shallow Concentrated Flow, Unpaved $K_v=16.1$ fps
2.8	275	Total			

Subcatchment EDA-1 (IMPERV):

Summary for Subcatchment EDA-1 (PERV):

Runoff = 0.28 cfs @ 1.32 hrs, Volume= 0.014 af, Depth= 0.07"
 Routed to Reach DP1-EX :


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NJ DEP 2-hr WQ Rainfall=1.25"

Area (sf)	CN	Description
102,351	74	>75% Grass cover, Good, HSG C
102,351		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.9	100	0.0140	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
2.2	401	0.0350	3.01		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
13.1	501	Total			

Subcatchment EDA-1 (PERV):

Hydrograph



Summary for Subcatchment EDA-2 (PERV.):

Runoff = 0.06 cfs @ 1.22 hrs, Volume= 0.003 af, Depth= 0.07"
 Routed to Reach DP2-EX :


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NJ DEP 2-hr WQ Rainfall=1.25"

Area (sf)	CN	Description
18,430	74	>75% Grass cover, Good, HSG C
18,430		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.1	100	0.0410	0.24		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.1	21	0.1050	5.22		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.2	121	Total			

Subcatchment EDA-2 (PERV.):

Hydrograph




Summary for Reach DP1-EX:

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.669 ac, 11.97% Impervious, Inflow Depth = 0.19" for WQ event
Inflow = 0.96 cfs @ 1.05 hrs, Volume= 0.042 af
Outflow = 0.96 cfs @ 1.05 hrs, Volume= 0.042 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Reach DP1-EX:**Hydrograph**




Summary for Reach DP2-EX:

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.423 ac, 0.00% Impervious, Inflow Depth = 0.07" for WQ event
Inflow = 0.06 cfs @ 1.22 hrs, Volume= 0.003 af
Outflow = 0.06 cfs @ 1.22 hrs, Volume= 0.003 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP2-EX:**Hydrograph**



Routing Diagram for 240924_42 ERW Waymaker
 Prepared by Colliers Engineering & Design, Printed 10/17/2024
 HydroCAD® 10.20-4b s/n 04431 © 2023 HydroCAD Software Solutions LLC

Project Notes

Rainfall events imported from "NRCS2-Rain.txt" for 1167 NJ Essex-D

Rainfall Events Listing (selected events)

Event#	Event Name	Storm Type	Curve	Mode	Duration (hours)	B/B	Depth (inches)	AMC
1	2-Year	NOAA 24-hr	D	Default	24.00	1	3.44	2
2	10-Year	NOAA 24-hr	D	Default	24.00	1	5.22	2
3	100-Year	NOAA 24-hr	D	Default	24.00	1	8.66	2
4	WQ	NJ DEP 2-hr		Default	2.00	1	1.25	2

Area Listing (selected nodes)

Area (acres)	CN	Description (subcatchment-numbers)
1.601	74	>75% Grass cover, Good, HSG C (PDA-1A (PERV), PDA-1B(PERV), PDA-1C(PERV), PDA-2 (PERV.))
0.644	89	Gravel roads, HSG C (PDA-1A (PERV), PDA-1B(PERV), PDA-1C(PERV), PDA-2 (PERV.))
0.355	98	Paved parking, HSG C (PDA-1B (IMPERV))
0.492	98	Roofs, HSG C (PDA-1B (IMPERV), PDA-1C(IMPERV))
3.092	84	TOTAL AREA

Soil Listing (selected nodes)

Area (acres)	Soil Group	Subcatchment Numbers
0.000	HSG A	
0.000	HSG B	
3.092	HSG C	PDA-1A (PERV), PDA-1B (IMPERV), PDA-1B(PERV), PDA-1C(IMPERV), PDA-1C(PERV), PDA-2 (PERV.)
0.000	HSG D	
0.000	Other	
3.092		TOTAL AREA

240924_42 ERW Waymaker

Prepared by Colliers Engineering & Design

Printed 10/17/2024

HydroCAD® 10.20-4b s/n 04431 © 2023 HydroCAD Software Solutions LLC

Page 6

Ground Covers (selected nodes)

HSG-A (acres)	HSG-B (acres)	HSG-C (acres)	HSG-D (acres)	Other (acres)	Total (acres)	Ground Cover	Subcatchment Numbers
0.000	0.000	1.601	0.000	0.000	1.601	>75% Grass cover, Good	PDA-1A (PERV), PDA-1B(P ERV), PDA-1C(PERV), PDA-2 (PERV.)
0.000	0.000	0.644	0.000	0.000	0.644	Gravel roads	PDA-1A (PERV), PDA-1B(P ERV), PDA-1C(PERV), PDA-2 (PERV.)
0.000	0.000	0.355	0.000	0.000	0.355	Paved parking	PDA-1B (IMPERV)
0.000	0.000	0.492	0.000	0.000	0.492	Roofs	PDA-1B (IMPERV)
							,
							PDA-1C(I MPERV)
0.000	0.000	3.092	0.000	0.000	3.092	TOTAL AREA	

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PDA-1A (PERV): (new Subcat) Runoff Area=13,167 sf 0.00% Impervious Runoff Depth=1.45"
Flow Length=203' Tc=5.9 min CN=78 Runoff=0.50 cfs 0.037 af

Subcatchment PDA-1B (IMPERV): (new Runoff Area=25,145 sf 100.00% Impervious Runoff Depth=3.21"
Flow Length=136' Tc=1.5 min CN=98 Runoff=2.07 cfs 0.154 af

Subcatchment PDA-1B(PERV): (new Subcat) Runoff Area=58,772 sf 0.00% Impervious Runoff Depth=1.52"
Flow Length=180' Tc=7.5 min CN=79 Runoff=2.24 cfs 0.171 af

Subcatchment PDA-1C(IMPERV): (new Runoff Area=11,760 sf 100.00% Impervious Runoff Depth=3.21"
Tc=1.0 min CN=98 Runoff=0.97 cfs 0.072 af

Subcatchment PDA-1C(PERV): (new Subcat) Runoff Area=18,423 sf 0.00% Impervious Runoff Depth=1.45"
Flow Length=123' Tc=7.2 min CN=78 Runoff=0.68 cfs 0.051 af

Subcatchment PDA-2 (PERV.): (new Subcat) Runoff Area=7,411 sf 0.00% Impervious Runoff Depth=1.32"
Flow Length=84' Slope=0.0833 '/' Tc=4.6 min CN=76 Runoff=0.26 cfs 0.019 af

Reach DP1-P: (new Reach) Inflow=1.41 cfs 0.389 af
Outflow=1.41 cfs 0.389 af

Reach DP2-P: (new Reach) Inflow=0.26 cfs 0.019 af
Outflow=0.26 cfs 0.019 af

Reach PDA-1B: (new Reach) Inflow=3.81 cfs 0.325 af
Outflow=3.81 cfs 0.325 af

Reach PDA-1C: (new Reach) Inflow=1.45 cfs 0.123 af
Outflow=1.45 cfs 0.123 af

Pond Basin 1: (new Pond) Peak Elev=14.76' Storage=0.164 af Inflow=3.81 cfs 0.325 af
Outflow=0.57 cfs 0.258 af

Pond Basin 2: (new Pond) Peak Elev=16.61' Storage=0.054 af Inflow=1.45 cfs 0.123 af
Outflow=0.67 cfs 0.095 af

Total Runoff Area = 3.092 ac Runoff Volume = 0.504 af Average Runoff Depth = 1.96"
72.60% Pervious = 2.245 ac 27.40% Impervious = 0.847 ac


Summary for Subcatchment PDA-1A (PERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 0.50 cfs @ 12.13 hrs, Volume= 0.037 af, Depth= 1.45"
 Routed to Reach DP1-P : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt= 0.05$ hrs
 NOAA 24-hr D 2-Year Rainfall=3.44"

Area (sf)	CN	Description
9,975	74	>75% Grass cover, Good, HSG C
3,192	89	Gravel roads, HSG C
13,167	78	Weighted Average
13,167		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	100	0.0725	0.30		Sheet Flow, Grass: Short $n= 0.150$ $P2= 3.44"$
0.3	103	0.1090	5.32		Shallow Concentrated Flow, Unpaved $K_v= 16.1$ fps
5.9	203	Total			

Subcatchment PDA-1A (PERV): (new Subcat)


Summary for Subcatchment PDA-1B (IMPERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 2.07 cfs @ 12.07 hrs, Volume= 0.154 af, Depth= 3.21"
 Routed to Reach PDA-1B : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 2-Year Rainfall=3.44"

Area (sf)	CN	Description
9,688	98	Roofs, HSG C
15,457	98	Paved parking, HSG C
25,145	98	Weighted Average
25,145		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	100	0.0200	1.43		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.44"
0.3	36	0.0139	2.39		Shallow Concentrated Flow, Paved Kv= 20.3 fps
1.5	136	Total			

Subcatchment PDA-1B (IMPERV): (new Subcat)


Summary for Subcatchment PDA-1B(PERV): (new Subcat)

Runoff = 2.24 cfs @ 12.15 hrs, Volume= 0.171 af, Depth= 1.52"
 Routed to Reach PDA-1B : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 2-Year Rainfall=3.44"

Area (sf)	CN	Description
39,275	74	>75% Grass cover, Good, HSG C
19,497	89	Gravel roads, HSG C
58,772	79	Weighted Average
58,772		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.2	100	0.0400	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.3	80	0.0812	4.59		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.5	180	Total			

Subcatchment PDA-1B(PERV): (new Subcat)


Summary for Subcatchment PDA-1C(IMPERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 0.97 cfs @ 12.06 hrs, Volume= 0.072 af, Depth= 3.21"
 Routed to Reach PDA-1C : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt= 0.05$ hrs
 NOAA 24-hr D 2-Year Rainfall=3.44"

Area (sf)	CN	Description
11,760	98	Roofs, HSG C
11,760		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.0					Direct Entry,

Subcatchment PDA-1C(IMPERV): (new Subcat)

Summary for Subcatchment PDA-1C(PERV): (new Subcat)

Runoff = 0.68 cfs @ 12.15 hrs, Volume= 0.051 af, Depth= 1.45"
 Routed to Reach PDA-1C : (new Reach)


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 2-Year Rainfall=3.44"

Area (sf)	CN	Description
4,377	89	Gravel roads, HSG C
14,046	74	>75% Grass cover, Good, HSG C
18,423	78	Weighted Average
18,423		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0	100	0.0425	0.24		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.2	23	0.0100	1.61		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.2	123	Total			

Subcatchment PDA-1C(PERV): (new Subcat)

Hydrograph



Summary for Subcatchment PDA-2 (PERV.): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 0.26 cfs @ 12.11 hrs, Volume= 0.019 af, Depth= 1.32"
 Routed to Reach DP2-P : (new Reach)


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 2-Year Rainfall=3.44"

Area (sf)	CN	Description
6,431	74	>75% Grass cover, Good, HSG C
980	89	Gravel roads, HSG C
7,411	76	Weighted Average
7,411		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	84	0.0833	0.30		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"

Subcatchment PDA-2 (PERV.): (new Subcat)

Hydrograph



Summary for Reach DP1-P: (new Reach)


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.922 ac, 29.00% Impervious, Inflow Depth > 1.60" for 2-Year event
Inflow = 1.41 cfs @ 12.23 hrs, Volume= 0.389 af
Outflow = 1.41 cfs @ 12.23 hrs, Volume= 0.389 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP1-P: (new Reach)

Hydrograph



Summary for Reach DP2-P: (new Reach)


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.170 ac, 0.00% Impervious, Inflow Depth = 1.32" for 2-Year event
Inflow = 0.26 cfs @ 12.11 hrs, Volume= 0.019 af
Outflow = 0.26 cfs @ 12.11 hrs, Volume= 0.019 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP2-P: (new Reach)

Hydrograph




Summary for Reach PDA-1B: (new Reach)

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 1.926 ac, 29.96% Impervious, Inflow Depth = 2.03" for 2-Year event
Inflow = 3.81 cfs @ 12.09 hrs, Volume= 0.325 af
Outflow = 3.81 cfs @ 12.09 hrs, Volume= 0.325 af, Atten= 0%, Lag= 0.0 min
Routed to Pond Basin 1 : (new Pond)

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Reach PDA-1B: (new Reach)

Summary for Reach PDA-1C: (new Reach)

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.693 ac, 38.96% Impervious, Inflow Depth = 2.14" for 2-Year event
Inflow = 1.45 cfs @ 12.08 hrs, Volume= 0.123 af
Outflow = 1.45 cfs @ 12.08 hrs, Volume= 0.123 af, Atten= 0%, Lag= 0.0 min
Routed to Pond Basin 2 : (new Pond)

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach PDA-1C: (new Reach)

Summary for Pond Basin 1: (new Pond)

Inflow Area = 1.926 ac, 29.96% Impervious, Inflow Depth = 2.03" for 2-Year event
 Inflow = 3.81 cfs @ 12.09 hrs, Volume= 0.325 af
 Outflow = 0.57 cfs @ 12.85 hrs, Volume= 0.258 af, Atten= 85%, Lag= 45.6 min
 Primary = 0.57 cfs @ 12.85 hrs, Volume= 0.258 af
 Routed to Reach DP1-P : (new Reach)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 Peak Elev= 14.76' @ 12.85 hrs Surf.Area= 0.121 ac Storage= 0.164 af

Plug-Flow detention time= 281.3 min calculated for 0.257 af (79% of inflow)
 Center-of-Mass det. time= 194.6 min (1,000.8 - 806.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	12.75'	0.169 af	37.08'W x 141.93'L x 5.50'H Field A 0.665 af Overall - 0.243 af Embedded = 0.421 af x 40.0% Voids
#2A	13.50'	0.243 af	ADS StormTech MC-3500 d +Cap x 95 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 95 Chambers in 5 Rows Cap Storage= 14.9 cf x 2 x 5 rows = 149.0 cf
0.412 af			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	13.80'	5.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	14.80'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Primary	17.50'	1.5' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Primary OutFlow Max=0.57 cfs @ 12.85 hrs HW=14.76' (Free Discharge)

- 1=Orifice/Grate (Orifice Controls 0.57 cfs @ 4.17 fps)
- 2=Orifice/Grate (Controls 0.00 cfs)
- 3=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

Pond Basin 1: (new Pond) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 5 rows = 149.0 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

19 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 139.93' Row Length +12.0" End Stone x 2 = 141.93' Base Length

5 Rows x 77.0" Wide + 9.0" Spacing x 4 + 12.0" Side Stone x 2 = 37.08' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

95 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 5 Rows = 10,594.4 cf Chamber Storage

28,947.8 cf Field - 10,594.4 cf Chambers = 18,353.4 cf Stone x 40.0% Voids = 7,341.3 cf Stone Storage

Chamber Storage + Stone Storage = 17,935.8 cf = 0.412 af


Overall Storage Efficiency = 62.0%

Overall System Size = 141.93' x 37.08' x 5.50'

95 Chambers


1,072.1 cy Field

679.8 cy Stone



Pond Basin 1: (new Pond)

Hydrograph



Summary for Pond Basin 2: (new Pond)

Inflow Area = 0.693 ac, 38.96% Impervious, Inflow Depth = 2.14" for 2-Year event
 Inflow = 1.45 cfs @ 12.08 hrs, Volume= 0.123 af
 Outflow = 0.67 cfs @ 12.26 hrs, Volume= 0.095 af, Atten= 54%, Lag= 10.6 min
 Primary = 0.67 cfs @ 12.26 hrs, Volume= 0.095 af
 Routed to Reach DP1-P : (new Reach)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 Peak Elev= 16.61' @ 12.26 hrs Surf.Area= 0.031 ac Storage= 0.054 af

Plug-Flow detention time= 232.3 min calculated for 0.095 af (77% of inflow)
 Center-of-Mass det. time= 139.4 min (935.4 - 796.0)

Volume	Invert	Avail.Storage	Storage Description
#1A	14.00'	0.029 af	34.75'W x 39.22'L x 3.50'H Field A 0.109 af Overall - 0.037 af Embedded = 0.073 af x 40.0% Voids
#2A	14.50'	0.037 af	ADS StormTech SC-740 +Cap x 35 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 35 Chambers in 7 Rows
		0.066 af	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	15.40'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	16.30'	6.0" Vert. Orifice/Grate X 2.00 C= 0.600 Limited to weir flow at low heads
#3	Primary	17.05'	3.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Primary OutFlow Max=0.66 cfs @ 12.26 hrs HW=16.61' (Free Discharge)

- 1=Orifice/Grate (Orifice Controls 0.17 cfs @ 5.07 fps)
- 2=Orifice/Grate (Orifice Controls 0.49 cfs @ 1.90 fps)
- 3=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

Pond Basin 2: (new Pond) - Chamber Wizard Field A**Chamber Model = ADS_StormTech SC-740 +Cap (ADS StormTech® SC-740 with cap length)**

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

5 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 37.22' Row Length +12.0" End Stone x 2 = 39.22' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

6.0" Stone Base + 30.0" Chamber Height + 6.0" Stone Cover = 3.50' Field Height

35 Chambers x 45.9 cf = 1,607.9 cf Chamber Storage

4,769.7 cf Field - 1,607.9 cf Chambers = 3,161.8 cf Stone x 40.0% Voids = 1,264.7 cf Stone Storage

Chamber Storage + Stone Storage = 2,872.6 cf = 0.066 af


Overall Storage Efficiency = 60.2%

Overall System Size = 39.22' x 34.75' x 3.50'

35 Chambers


176.7 cy Field

117.1 cy Stone



Pond Basin 2: (new Pond)

Hydrograph



Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PDA-1A (PERV): (new Subcat) Runoff Area=13,167 sf 0.00% Impervious Runoff Depth=2.90"
Flow Length=203' Tc=5.9 min CN=78 Runoff=1.00 cfs 0.073 af

Subcatchment PDA-1B (IMPERV): (new Runoff Area=25,145 sf 100.00% Impervious Runoff Depth=4.98"
Flow Length=136' Tc=1.5 min CN=98 Runoff=3.16 cfs 0.240 af

Subcatchment PDA-1B(PERV): (new Subcat) Runoff Area=58,772 sf 0.00% Impervious Runoff Depth=2.99"
Flow Length=180' Tc=7.5 min CN=79 Runoff=4.41 cfs 0.336 af

Subcatchment PDA-1C(IMPERV): (new Runoff Area=11,760 sf 100.00% Impervious Runoff Depth=4.98"
Tc=1.0 min CN=98 Runoff=1.48 cfs 0.112 af

Subcatchment PDA-1C(PERV): (new Subcat) Runoff Area=18,423 sf 0.00% Impervious Runoff Depth=2.90"
Flow Length=123' Tc=7.2 min CN=78 Runoff=1.35 cfs 0.102 af

Subcatchment PDA-2 (PERV.): (new Subcat) Runoff Area=7,411 sf 0.00% Impervious Runoff Depth=2.72"
Flow Length=84' Slope=0.0833 '/' Tc=4.6 min CN=76 Runoff=0.55 cfs 0.039 af

Reach DP1-P: (new Reach) Inflow=4.41 cfs 0.767 af
Outflow=4.41 cfs 0.767 af

Reach DP2-P: (new Reach) Inflow=0.55 cfs 0.039 af
Outflow=0.55 cfs 0.039 af

Reach PDA-1B: (new Reach) Inflow=6.72 cfs 0.576 af
Outflow=6.72 cfs 0.576 af

Reach PDA-1C: (new Reach) Inflow=2.49 cfs 0.214 af
Outflow=2.49 cfs 0.214 af

Pond Basin 1: (new Pond) Peak Elev=15.76' Storage=0.257 af Inflow=6.72 cfs 0.576 af
Outflow=1.66 cfs 0.509 af

Pond Basin 2: (new Pond) Peak Elev=17.21' Storage=0.062 af Inflow=2.49 cfs 0.214 af
Outflow=2.28 cfs 0.186 af

Total Runoff Area = 3.092 ac Runoff Volume = 0.902 af Average Runoff Depth = 3.50"
72.60% Pervious = 2.245 ac 27.40% Impervious = 0.847 ac


Summary for Subcatchment PDA-1A (PERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 1.00 cfs @ 12.13 hrs, Volume= 0.073 af, Depth= 2.90"
 Routed to Reach DP1-P : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 10-Year Rainfall=5.22"

Area (sf)	CN	Description
9,975	74	>75% Grass cover, Good, HSG C
3,192	89	Gravel roads, HSG C
13,167	78	Weighted Average
13,167		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	100	0.0725	0.30		Sheet Flow, Grass: Short $n=0.150$ $P2=3.44"$
0.3	103	0.1090	5.32		Shallow Concentrated Flow, Unpaved $K_v=16.1$ fps
5.9	203	Total			

Subcatchment PDA-1A (PERV): (new Subcat)


Summary for Subcatchment PDA-1B (IMPERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 3.16 cfs @ 12.07 hrs, Volume= 0.240 af, Depth= 4.98"
 Routed to Reach PDA-1B : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 10-Year Rainfall=5.22"

Area (sf)	CN	Description
9,688	98	Roofs, HSG C
15,457	98	Paved parking, HSG C
25,145	98	Weighted Average
25,145		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	100	0.0200	1.43		Sheet Flow, Smooth surfaces $n=0.011$ $P2=3.44"$
0.3	36	0.0139	2.39		Shallow Concentrated Flow, Paved $K_v=20.3$ fps
1.5	136	Total			

Subcatchment PDA-1B (IMPERV): (new Subcat)


Summary for Subcatchment PDA-1B(PERV): (new Subcat)

Runoff = 4.41 cfs @ 12.15 hrs, Volume= 0.336 af, Depth= 2.99"
 Routed to Reach PDA-1B : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 10-Year Rainfall=5.22"

Area (sf)	CN	Description
39,275	74	>75% Grass cover, Good, HSG C
19,497	89	Gravel roads, HSG C
58,772	79	Weighted Average
58,772		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.2	100	0.0400	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.3	80	0.0812	4.59		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.5	180	Total			

Subcatchment PDA-1B(PERV): (new Subcat)


Summary for Subcatchment PDA-1C(IMPERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 1.48 cfs @ 12.06 hrs, Volume= 0.112 af, Depth= 4.98"
 Routed to Reach PDA-1C : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 10-Year Rainfall=5.22"

Area (sf)	CN	Description
11,760	98	Roofs, HSG C
11,760		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.0					Direct Entry,

Subcatchment PDA-1C(IMPERV): (new Subcat)


Summary for Subcatchment PDA-1C(PERV): (new Subcat)

Runoff = 1.35 cfs @ 12.14 hrs, Volume= 0.102 af, Depth= 2.90"
 Routed to Reach PDA-1C : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 10-Year Rainfall=5.22"

Area (sf)	CN	Description
4,377	89	Gravel roads, HSG C
14,046	74	>75% Grass cover, Good, HSG C
18,423	78	Weighted Average
18,423		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0	100	0.0425	0.24		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.2	23	0.0100	1.61		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.2	123	Total			

Subcatchment PDA-1C(PERV): (new Subcat)

Summary for Subcatchment PDA-2 (PERV.): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 0.55 cfs @ 12.11 hrs, Volume= 0.039 af, Depth= 2.72"
 Routed to Reach DP2-P : (new Reach)


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 10-Year Rainfall=5.22"

Area (sf)	CN	Description
6,431	74	>75% Grass cover, Good, HSG C
980	89	Gravel roads, HSG C
7,411	76	Weighted Average
7,411		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	84	0.0833	0.30		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"

Subcatchment PDA-2 (PERV.): (new Subcat)

Hydrograph



Summary for Reach DP1-P: (new Reach)


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.922 ac, 29.00% Impervious, Inflow Depth = 3.15" for 10-Year event
Inflow = 4.41 cfs @ 12.14 hrs, Volume= 0.767 af
Outflow = 4.41 cfs @ 12.14 hrs, Volume= 0.767 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP1-P: (new Reach)

Hydrograph



Summary for Reach DP2-P: (new Reach)


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.170 ac, 0.00% Impervious, Inflow Depth = 2.72" for 10-Year event
Inflow = 0.55 cfs @ 12.11 hrs, Volume= 0.039 af
Outflow = 0.55 cfs @ 12.11 hrs, Volume= 0.039 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP2-P: (new Reach)

Hydrograph




Summary for Reach PDA-1B: (new Reach)

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 1.926 ac, 29.96% Impervious, Inflow Depth = 3.59" for 10-Year event
Inflow = 6.72 cfs @ 12.10 hrs, Volume= 0.576 af
Outflow = 6.72 cfs @ 12.10 hrs, Volume= 0.576 af, Atten= 0%, Lag= 0.0 min
Routed to Pond Basin 1 : (new Pond)

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Reach PDA-1B: (new Reach)

Summary for Reach PDA-1C: (new Reach)

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.693 ac, 38.96% Impervious, Inflow Depth = 3.71" for 10-Year event
Inflow = 2.49 cfs @ 12.08 hrs, Volume= 0.214 af
Outflow = 2.49 cfs @ 12.08 hrs, Volume= 0.214 af, Atten= 0%, Lag= 0.0 min
Routed to Pond Basin 2 : (new Pond)

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach PDA-1C: (new Reach)

Summary for Pond Basin 1: (new Pond)

Inflow Area = 1.926 ac, 29.96% Impervious, Inflow Depth = 3.59" for 10-Year event
 Inflow = 6.72 cfs @ 12.10 hrs, Volume= 0.576 af
 Outflow = 1.66 cfs @ 12.47 hrs, Volume= 0.509 af, Atten= 75%, Lag= 22.3 min
 Primary = 1.66 cfs @ 12.47 hrs, Volume= 0.509 af
 Routed to Reach DP1-P : (new Reach)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 Peak Elev= 15.76' @ 12.47 hrs Surf.Area= 0.121 ac Storage= 0.257 af

Plug-Flow detention time= 210.6 min calculated for 0.508 af (88% of inflow)
 Center-of-Mass det. time= 153.1 min (949.3 - 796.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	12.75'	0.169 af	37.08'W x 141.93'L x 5.50'H Field A 0.665 af Overall - 0.243 af Embedded = 0.421 af x 40.0% Voids
#2A	13.50'	0.243 af	ADS StormTech MC-3500 d +Cap x 95 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 95 Chambers in 5 Rows Cap Storage= 14.9 cf x 2 x 5 rows = 149.0 cf
0.412 af			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	13.80'	5.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	14.80'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Primary	17.50'	1.5' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Primary OutFlow Max=1.66 cfs @ 12.47 hrs HW=15.76' (Free Discharge)

- ↑ **1=Orifice/Grate** (Orifice Controls 0.87 cfs @ 6.37 fps)
- ↑ **2=Orifice/Grate** (Orifice Controls 0.80 cfs @ 4.05 fps)
- ↑ **3=Sharp-Crested Rectangular Weir** (Controls 0.00 cfs)

Pond Basin 1: (new Pond) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 5 rows = 149.0 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

19 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 139.93' Row Length +12.0" End Stone x 2 = 141.93' Base Length

5 Rows x 77.0" Wide + 9.0" Spacing x 4 + 12.0" Side Stone x 2 = 37.08' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

95 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 5 Rows = 10,594.4 cf Chamber Storage

28,947.8 cf Field - 10,594.4 cf Chambers = 18,353.4 cf Stone x 40.0% Voids = 7,341.3 cf Stone Storage

Chamber Storage + Stone Storage = 17,935.8 cf = 0.412 af


Overall Storage Efficiency = 62.0%

Overall System Size = 141.93' x 37.08' x 5.50'

95 Chambers


1,072.1 cy Field

679.8 cy Stone



Pond Basin 1: (new Pond)

Hydrograph



Summary for Pond Basin 2: (new Pond)

Inflow Area = 0.693 ac, 38.96% Impervious, Inflow Depth = 3.71" for 10-Year event
 Inflow = 2.49 cfs @ 12.08 hrs, Volume= 0.214 af
 Outflow = 2.28 cfs @ 12.12 hrs, Volume= 0.186 af, Atten= 8%, Lag= 2.3 min
 Primary = 2.28 cfs @ 12.12 hrs, Volume= 0.186 af
 Routed to Reach DP1-P : (new Reach)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 Peak Elev= 17.21' @ 12.12 hrs Surf.Area= 0.031 ac Storage= 0.062 af

Plug-Flow detention time= 165.3 min calculated for 0.186 af (87% of inflow)
 Center-of-Mass det. time= 101.2 min (888.9 - 787.7)

Volume	Invert	Avail.Storage	Storage Description
#1A	14.00'	0.029 af	34.75'W x 39.22'L x 3.50'H Field A 0.109 af Overall - 0.037 af Embedded = 0.073 af x 40.0% Voids
#2A	14.50'	0.037 af	ADS StormTech SC-740 +Cap x 35 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 35 Chambers in 7 Rows
		0.066 af	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	15.40'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	16.30'	6.0" Vert. Orifice/Grate X 2.00 C= 0.600 Limited to weir flow at low heads
#3	Primary	17.05'	3.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Primary OutFlow Max=2.19 cfs @ 12.12 hrs HW=17.18' (Free Discharge)

- 1=Orifice/Grate (Orifice Controls 0.21 cfs @ 6.24 fps)
- 2=Orifice/Grate (Orifice Controls 1.50 cfs @ 3.83 fps)
- 3=Sharp-Crested Rectangular Weir (Weir Controls 0.47 cfs @ 1.19 fps)

Pond Basin 2: (new Pond) - Chamber Wizard Field A**Chamber Model = ADS_StormTech SC-740 +Cap (ADS StormTech® SC-740 with cap length)**

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

5 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 37.22' Row Length +12.0" End Stone x 2 = 39.22' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

6.0" Stone Base + 30.0" Chamber Height + 6.0" Stone Cover = 3.50' Field Height

35 Chambers x 45.9 cf = 1,607.9 cf Chamber Storage

4,769.7 cf Field - 1,607.9 cf Chambers = 3,161.8 cf Stone x 40.0% Voids = 1,264.7 cf Stone Storage

Chamber Storage + Stone Storage = 2,872.6 cf = 0.066 af


Overall Storage Efficiency = 60.2%

Overall System Size = 39.22' x 34.75' x 3.50'

35 Chambers


176.7 cy Field

117.1 cy Stone



Pond Basin 2: (new Pond)

Hydrograph



Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PDA-1A (PERV): (new Subcat) Runoff Area=13,167 sf 0.00% Impervious Runoff Depth=6.00"
Flow Length=203' Tc=5.9 min CN=78 Runoff=2.01 cfs 0.151 af

Subcatchment PDA-1B (IMPERV): (new Runoff Area=25,145 sf 100.00% Impervious Runoff Depth=8.42"
Flow Length=136' Tc=1.5 min CN=98 Runoff=5.25 cfs 0.405 af

Subcatchment PDA-1B(PERV): (new Subcat) Runoff Area=58,772 sf 0.00% Impervious Runoff Depth=6.13"
Flow Length=180' Tc=7.5 min CN=79 Runoff=8.79 cfs 0.689 af

Subcatchment PDA-1C(IMPERV): (new Runoff Area=11,760 sf 100.00% Impervious Runoff Depth=8.42"
Tc=1.0 min CN=98 Runoff=2.47 cfs 0.189 af

Subcatchment PDA-1C(PERV): (new Subcat) Runoff Area=18,423 sf 0.00% Impervious Runoff Depth=6.00"
Flow Length=123' Tc=7.2 min CN=78 Runoff=2.73 cfs 0.212 af

Subcatchment PDA-2 (PERV.): (new Subcat) Runoff Area=7,411 sf 0.00% Impervious Runoff Depth=5.76"
Flow Length=84' Slope=0.0833 '/' Tc=4.6 min CN=76 Runoff=1.14 cfs 0.082 af

Reach DP1-P: (new Reach) Inflow=9.24 cfs 1.550 af
Outflow=9.24 cfs 1.550 af

Reach DP2-P: (new Reach) Inflow=1.14 cfs 0.082 af
Outflow=1.14 cfs 0.082 af

Reach PDA-1B: (new Reach) Inflow=12.54 cfs 1.094 af
Outflow=12.54 cfs 1.094 af

Reach PDA-1C: (new Reach) Inflow=4.58 cfs 0.401 af
Outflow=4.58 cfs 0.401 af

Pond Basin 1: (new Pond) Peak Elev=18.25' Storage=0.412 af Inflow=12.54 cfs 1.094 af
Outflow=5.92 cfs 1.026 af

Pond Basin 2: (new Pond) Peak Elev=17.46' Storage=0.065 af Inflow=4.58 cfs 0.401 af
Outflow=4.52 cfs 0.373 af

Total Runoff Area = 3.092 ac Runoff Volume = 1.728 af Average Runoff Depth = 6.71"
72.60% Pervious = 2.245 ac 27.40% Impervious = 0.847 ac


Summary for Subcatchment PDA-1A (PERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 2.01 cfs @ 12.13 hrs, Volume= 0.151 af, Depth= 6.00"
 Routed to Reach DP1-P : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 100-Year Rainfall=8.66"

Area (sf)	CN	Description
9,975	74	>75% Grass cover, Good, HSG C
3,192	89	Gravel roads, HSG C
13,167	78	Weighted Average
13,167		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	100	0.0725	0.30		Sheet Flow, Grass: Short $n=0.150$ $P2=3.44"$
0.3	103	0.1090	5.32		Shallow Concentrated Flow, Unpaved $K_v=16.1$ fps
5.9	203	Total			

Subcatchment PDA-1A (PERV): (new Subcat)


Summary for Subcatchment PDA-1B (IMPERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 5.25 cfs @ 12.07 hrs, Volume= 0.405 af, Depth= 8.42"
 Routed to Reach PDA-1B : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 100-Year Rainfall=8.66"

Area (sf)	CN	Description
9,688	98	Roofs, HSG C
15,457	98	Paved parking, HSG C
25,145	98	Weighted Average
25,145		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	100	0.0200	1.43		Sheet Flow, Smooth surfaces $n=0.011$ $P2=3.44"$
0.3	36	0.0139	2.39		Shallow Concentrated Flow, Paved $K_v=20.3$ fps
1.5	136	Total			

Subcatchment PDA-1B (IMPERV): (new Subcat)

Summary for Subcatchment PDA-1B(PERV): (new Subcat)

Runoff = 8.79 cfs @ 12.14 hrs, Volume= 0.689 af, Depth= 6.13"
 Routed to Reach PDA-1B : (new Reach)


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 100-Year Rainfall=8.66"

Area (sf)	CN	Description
39,275	74	>75% Grass cover, Good, HSG C
19,497	89	Gravel roads, HSG C
58,772	79	Weighted Average
58,772		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.2	100	0.0400	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.3	80	0.0812	4.59		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.5	180	Total			

Subcatchment PDA-1B(PERV): (new Subcat)

Hydrograph




Summary for Subcatchment PDA-1C(IMPERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 2.47 cfs @ 12.06 hrs, Volume= 0.189 af, Depth= 8.42"
 Routed to Reach PDA-1C : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 100-Year Rainfall=8.66"

Area (sf)	CN	Description
11,760	98	Roofs, HSG C
11,760		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.0					Direct Entry,

Subcatchment PDA-1C(IMPERV): (new Subcat)


Summary for Subcatchment PDA-1C(PERV): (new Subcat)

Runoff = 2.73 cfs @ 12.14 hrs, Volume= 0.212 af, Depth= 6.00"
 Routed to Reach PDA-1C : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NOAA 24-hr D 100-Year Rainfall=8.66"

Area (sf)	CN	Description
4,377	89	Gravel roads, HSG C
14,046	74	>75% Grass cover, Good, HSG C
18,423	78	Weighted Average
18,423		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0	100	0.0425	0.24		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.2	23	0.0100	1.61		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.2	123	Total			

Subcatchment PDA-1C(PERV): (new Subcat)


Summary for Subcatchment PDA-2 (PERV.): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 1.14 cfs @ 12.11 hrs, Volume= 0.082 af, Depth= 5.76"
 Routed to Reach DP2-P : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NOAA 24-hr D 100-Year Rainfall=8.66"

Area (sf)	CN	Description
6,431	74	>75% Grass cover, Good, HSG C
980	89	Gravel roads, HSG C
7,411	76	Weighted Average
7,411		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	84	0.0833	0.30		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"


Subcatchment PDA-2 (PERV.): (new Subcat)

Summary for Reach DP1-P: (new Reach)

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.922 ac, 29.00% Impervious, Inflow Depth = 6.37" for 100-Year event
Inflow = 9.24 cfs @ 12.22 hrs, Volume= 1.550 af
Outflow = 9.24 cfs @ 12.22 hrs, Volume= 1.550 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP1-P: (new Reach)

Summary for Reach DP2-P: (new Reach)


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.170 ac, 0.00% Impervious, Inflow Depth = 5.76" for 100-Year event
Inflow = 1.14 cfs @ 12.11 hrs, Volume= 0.082 af
Outflow = 1.14 cfs @ 12.11 hrs, Volume= 0.082 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP2-P: (new Reach)

Hydrograph




Summary for Reach PDA-1B: (new Reach)

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 1.926 ac, 29.96% Impervious, Inflow Depth = 6.81" for 100-Year event
Inflow = 12.54 cfs @ 12.10 hrs, Volume= 1.094 af
Outflow = 12.54 cfs @ 12.10 hrs, Volume= 1.094 af, Atten= 0%, Lag= 0.0 min
Routed to Pond Basin 1 : (new Pond)

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Reach PDA-1B: (new Reach)

Summary for Reach PDA-1C: (new Reach)

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.693 ac, 38.96% Impervious, Inflow Depth = 6.95" for 100-Year event
Inflow = 4.58 cfs @ 12.09 hrs, Volume= 0.401 af
Outflow = 4.58 cfs @ 12.09 hrs, Volume= 0.401 af, Atten= 0%, Lag= 0.0 min
Routed to Pond Basin 2 : (new Pond)

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach PDA-1C: (new Reach)

Summary for Pond Basin 1: (new Pond)

Inflow Area = 1.926 ac, 29.96% Impervious, Inflow Depth = 6.81" for 100-Year event
 Inflow = 12.54 cfs @ 12.10 hrs, Volume= 1.094 af
 Outflow = 5.92 cfs @ 12.27 hrs, Volume= 1.026 af, Atten= 53%, Lag= 10.3 min
 Primary = 5.92 cfs @ 12.27 hrs, Volume= 1.026 af
 Routed to Reach DP1-P : (new Reach)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 Peak Elev= 18.25' @ 12.27 hrs Surf.Area= 0.121 ac Storage= 0.412 af

Plug-Flow detention time= 156.3 min calculated for 1.025 af (94% of inflow)
 Center-of-Mass det. time= 122.6 min (905.8 - 783.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	12.75'	0.169 af	37.08'W x 141.93'L x 5.50'H Field A 0.665 af Overall - 0.243 af Embedded = 0.421 af x 40.0% Voids
#2A	13.50'	0.243 af	ADS StormTech MC-3500 d +Cap x 95 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 95 Chambers in 5 Rows Cap Storage= 14.9 cf x 2 x 5 rows = 149.0 cf
0.412 af			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	13.80'	5.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	14.80'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Primary	17.50'	1.5' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Primary OutFlow Max=5.78 cfs @ 12.27 hrs HW=18.23' (Free Discharge)

- 1=Orifice/Grate (Orifice Controls 1.35 cfs @ 9.89 fps)
- 2=Orifice/Grate (Orifice Controls 1.69 cfs @ 8.58 fps)
- 3=Sharp-Crested Rectangular Weir (Weir Controls 2.75 cfs @ 2.79 fps)

Pond Basin 1: (new Pond) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 5 rows = 149.0 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

19 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 139.93' Row Length +12.0" End Stone x 2 = 141.93' Base Length

5 Rows x 77.0" Wide + 9.0" Spacing x 4 + 12.0" Side Stone x 2 = 37.08' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

95 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 5 Rows = 10,594.4 cf Chamber Storage

28,947.8 cf Field - 10,594.4 cf Chambers = 18,353.4 cf Stone x 40.0% Voids = 7,341.3 cf Stone Storage

Chamber Storage + Stone Storage = 17,935.8 cf = 0.412 af


Overall Storage Efficiency = 62.0%

Overall System Size = 141.93' x 37.08' x 5.50'

95 Chambers


1,072.1 cy Field

679.8 cy Stone



Pond Basin 1: (new Pond)

Hydrograph



Summary for Pond Basin 2: (new Pond)

Inflow Area = 0.693 ac, 38.96% Impervious, Inflow Depth = 6.95" for 100-Year event
 Inflow = 4.58 cfs @ 12.09 hrs, Volume= 0.401 af
 Outflow = 4.52 cfs @ 12.10 hrs, Volume= 0.373 af, Atten= 1%, Lag= 1.0 min
 Primary = 4.52 cfs @ 12.10 hrs, Volume= 0.373 af
 Routed to Reach DP1-P : (new Reach)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 Peak Elev= 17.46' @ 12.10 hrs Surf.Area= 0.031 ac Storage= 0.065 af

Plug-Flow detention time= 114.8 min calculated for 0.372 af (93% of inflow)
 Center-of-Mass det. time= 75.7 min (852.3 - 776.6)

Volume	Invert	Avail.Storage	Storage Description
#1A	14.00'	0.029 af	34.75'W x 39.22'L x 3.50'H Field A 0.109 af Overall - 0.037 af Embedded = 0.073 af x 40.0% Voids
#2A	14.50'	0.037 af	ADS StormTech SC-740 +Cap x 35 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 35 Chambers in 7 Rows
		0.066 af	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	15.40'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	16.30'	6.0" Vert. Orifice/Grate X 2.00 C= 0.600 Limited to weir flow at low heads
#3	Primary	17.05'	3.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Primary OutFlow Max=4.48 cfs @ 12.10 hrs HW=17.45' (Free Discharge)

- 1=Orifice/Grate (Orifice Controls 0.23 cfs @ 6.72 fps)
- 2=Orifice/Grate (Orifice Controls 1.80 cfs @ 4.58 fps)
- 3=Sharp-Crested Rectangular Weir (Weir Controls 2.45 cfs @ 2.08 fps)

Pond Basin 2: (new Pond) - Chamber Wizard Field A**Chamber Model = ADS_StormTech SC-740 +Cap (ADS StormTech® SC-740 with cap length)**

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

5 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 37.22' Row Length +12.0" End Stone x 2 = 39.22' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

6.0" Stone Base + 30.0" Chamber Height + 6.0" Stone Cover = 3.50' Field Height

35 Chambers x 45.9 cf = 1,607.9 cf Chamber Storage

4,769.7 cf Field - 1,607.9 cf Chambers = 3,161.8 cf Stone x 40.0% Voids = 1,264.7 cf Stone Storage

Chamber Storage + Stone Storage = 2,872.6 cf = 0.066 af


Overall Storage Efficiency = 60.2%

Overall System Size = 39.22' x 34.75' x 3.50'

35 Chambers


176.7 cy Field

117.1 cy Stone



Pond Basin 2: (new Pond)

Hydrograph



Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment PDA-1A (PERV): (new Subcat) Runoff Area=13,167 sf 0.00% Impervious Runoff Depth=0.13"
Flow Length=203' Tc=5.9 min CN=78 Runoff=0.11 cfs 0.003 af

Subcatchment PDA-1B (IMPERV): (new Runoff Area=25,145 sf 100.00% Impervious Runoff Depth=1.03"
Flow Length=136' Tc=1.5 min CN=98 Runoff=1.79 cfs 0.050 af

Subcatchment PDA-1B(PERV): (new Subcat) Runoff Area=58,772 sf 0.00% Impervious Runoff Depth=0.15"
Flow Length=180' Tc=7.5 min CN=79 Runoff=0.51 cfs 0.017 af

Subcatchment PDA-1C(IMPERV): (new Runoff Area=11,760 sf 100.00% Impervious Runoff Depth=1.03"
Tc=1.0 min CN=98 Runoff=0.85 cfs 0.023 af

Subcatchment PDA-1C(PERV): (new Subcat) Runoff Area=18,423 sf 0.00% Impervious Runoff Depth=0.13"
Flow Length=123' Tc=7.2 min CN=78 Runoff=0.14 cfs 0.005 af

Subcatchment PDA-2 (PERV.): (new Subcat) Runoff Area=7,411 sf 0.00% Impervious Runoff Depth=0.10"
Flow Length=84' Slope=0.0833 '/' Tc=4.6 min CN=76 Runoff=0.04 cfs 0.001 af

Reach DP1-P: (new Reach) Inflow=0.11 cfs 0.003 af
Outflow=0.11 cfs 0.003 af

Reach DP2-P: (new Reach) Inflow=0.04 cfs 0.001 af
Outflow=0.04 cfs 0.001 af

Reach PDA-1B: (new Reach) Inflow=1.82 cfs 0.067 af
Outflow=1.82 cfs 0.067 af

Reach PDA-1C: (new Reach) Inflow=0.85 cfs 0.028 af
Outflow=0.85 cfs 0.028 af

Pond Basin 1: (new Pond) Peak Elev=13.80' Storage=0.067 af Inflow=1.82 cfs 0.067 af
Outflow=0.00 cfs 0.000 af

Pond Basin 2: (new Pond) Peak Elev=15.38' Storage=0.028 af Inflow=0.85 cfs 0.028 af
Outflow=0.00 cfs 0.000 af

Total Runoff Area = 3.092 ac Runoff Volume = 0.100 af Average Runoff Depth = 0.39"
72.60% Pervious = 2.245 ac 27.40% Impervious = 0.847 ac

Summary for Subcatchment PDA-1A (PERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 0.11 cfs @ 1.16 hrs, Volume= 0.003 af, Depth= 0.13"
 Routed to Reach DP1-P : (new Reach)


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NJ DEP 2-hr WQ Rainfall=1.25"

Area (sf)	CN	Description
9,975	74	>75% Grass cover, Good, HSG C
3,192	89	Gravel roads, HSG C
13,167	78	Weighted Average
13,167		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.6	100	0.0725	0.30		Sheet Flow, Grass: Short $n=0.150$ $P2=3.44"$
0.3	103	0.1090	5.32		Shallow Concentrated Flow, Unpaved $K_v=16.1$ fps
5.9	203	Total			

Subcatchment PDA-1A (PERV): (new Subcat)

Hydrograph




Summary for Subcatchment PDA-1B (IMPERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 1.79 cfs @ 1.03 hrs, Volume= 0.050 af, Depth= 1.03"
 Routed to Reach PDA-1B : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt=0.05$ hrs
 NJ DEP 2-hr WQ Rainfall=1.25"

Area (sf)	CN	Description
9,688	98	Roofs, HSG C
15,457	98	Paved parking, HSG C
25,145	98	Weighted Average
25,145		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.2	100	0.0200	1.43		Sheet Flow, Smooth surfaces $n=0.011$ $P2=3.44"$
0.3	36	0.0139	2.39		Shallow Concentrated Flow, Paved $K_v=20.3$ fps
1.5	136	Total			

Subcatchment PDA-1B (IMPERV): (new Subcat)

Summary for Subcatchment PDA-1B(PERV): (new Subcat)

Runoff = 0.51 cfs @ 1.17 hrs, Volume= 0.017 af, Depth= 0.15"
 Routed to Reach PDA-1B : (new Reach)


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NJ DEP 2-hr WQ Rainfall=1.25"

Area (sf)	CN	Description
39,275	74	>75% Grass cover, Good, HSG C
19,497	89	Gravel roads, HSG C
58,772	79	Weighted Average
58,772		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.2	100	0.0400	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.3	80	0.0812	4.59		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.5	180	Total			

Subcatchment PDA-1B(PERV): (new Subcat)

Hydrograph




Summary for Subcatchment PDA-1C(IMPERV): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 0.85 cfs @ 1.03 hrs, Volume= 0.023 af, Depth= 1.03"
 Routed to Reach PDA-1C : (new Reach)

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt= 0.05$ hrs
 NJ DEP 2-hr WQ Rainfall=1.25"

Area (sf)	CN	Description
11,760	98	Roofs, HSG C
11,760		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.0					Direct Entry,

Subcatchment PDA-1C(IMPERV): (new Subcat)

Summary for Subcatchment PDA-1C(PERV): (new Subcat)

Runoff = 0.14 cfs @ 1.17 hrs, Volume= 0.005 af, Depth= 0.13"
 Routed to Reach PDA-1C : (new Reach)


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 NJ DEP 2-hr WQ Rainfall=1.25"

Area (sf)	CN	Description
4,377	89	Gravel roads, HSG C
14,046	74	>75% Grass cover, Good, HSG C
18,423	78	Weighted Average
18,423		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.0	100	0.0425	0.24		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"
0.2	23	0.0100	1.61		Shallow Concentrated Flow, Unpaved Kv= 16.1 fps
7.2	123	Total			

Subcatchment PDA-1C(PERV): (new Subcat)

Hydrograph



Summary for Subcatchment PDA-2 (PERV.): (new Subcat)[49] Hint: $T_c < 2dt$ may require smaller dt

Runoff = 0.04 cfs @ 1.16 hrs, Volume= 0.001 af, Depth= 0.10"
 Routed to Reach DP2-P : (new Reach)


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, $dt= 0.05$ hrs
 NJ DEP 2-hr WQ Rainfall=1.25"

Area (sf)	CN	Description
6,431	74	>75% Grass cover, Good, HSG C
980	89	Gravel roads, HSG C
7,411	76	Weighted Average
7,411		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	84	0.0833	0.30		Sheet Flow, Grass: Short n= 0.150 P2= 3.44"

Subcatchment PDA-2 (PERV.): (new Subcat)

Hydrograph



Summary for Reach DP1-P: (new Reach)


[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 2.922 ac, 29.00% Impervious, Inflow Depth = 0.01" for WQ event
Inflow = 0.11 cfs @ 1.16 hrs, Volume= 0.003 af
Outflow = 0.11 cfs @ 1.16 hrs, Volume= 0.003 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach DP1-P: (new Reach)

Hydrograph




Summary for Reach DP2-P: (new Reach)

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.170 ac, 0.00% Impervious, Inflow Depth = 0.10" for WQ event
Inflow = 0.04 cfs @ 1.16 hrs, Volume= 0.001 af
Outflow = 0.04 cfs @ 1.16 hrs, Volume= 0.001 af, Atten= 0%, Lag= 0.0 min

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Reach DP2-P: (new Reach)**Hydrograph**

Summary for Reach PDA-1B: (new Reach)

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 1.926 ac, 29.96% Impervious, Inflow Depth = 0.42" for WQ event
Inflow = 1.82 cfs @ 1.04 hrs, Volume= 0.067 af
Outflow = 1.82 cfs @ 1.04 hrs, Volume= 0.067 af, Atten= 0%, Lag= 0.0 min
Routed to Pond Basin 1 : (new Pond)

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Reach PDA-1B: (new Reach)

Summary for Reach PDA-1C: (new Reach)

[40] Hint: Not Described (Outflow=Inflow)

Inflow Area = 0.693 ac, 38.96% Impervious, Inflow Depth = 0.48" for WQ event
Inflow = 0.85 cfs @ 1.03 hrs, Volume= 0.028 af
Outflow = 0.85 cfs @ 1.03 hrs, Volume= 0.028 af, Atten= 0%, Lag= 0.0 min
Routed to Pond Basin 2 : (new Pond)

Routing by Stor-Ind+Trans method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Reach PDA-1C: (new Reach)

Summary for Pond Basin 1: (new Pond)

Inflow Area = 1.926 ac, 29.96% Impervious, Inflow Depth = 0.42" for WQ event
 Inflow = 1.82 cfs @ 1.04 hrs, Volume= 0.067 af
 Outflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 100%, Lag= 0.0 min
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Reach DP1-P : (new Reach)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 Peak Elev= 13.80' @ 2.45 hrs Surf.Area= 0.121 ac Storage= 0.067 af

Plug-Flow detention time= (not calculated: initial storage exceeds outflow)
 Center-of-Mass det. time= (not calculated: no outflow)

Volume	Invert	Avail.Storage	Storage Description
#1A	12.75'	0.169 af	37.08'W x 141.93'L x 5.50'H Field A 0.665 af Overall - 0.243 af Embedded = 0.421 af x 40.0% Voids
#2A	13.50'	0.243 af	ADS StormTech MC-3500 d +Cap x 95 Inside #1 Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap 95 Chambers in 5 Rows Cap Storage= 14.9 cf x 2 x 5 rows = 149.0 cf
0.412 af			Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	13.80'	5.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	14.80'	6.0" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#3	Primary	17.50'	1.5' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=12.75' (Free Discharge)

- 1=Orifice/Grate (Controls 0.00 cfs)
- 2=Orifice/Grate (Controls 0.00 cfs)
- 3=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

Pond Basin 1: (new Pond) - Chamber Wizard Field A

Chamber Model = ADS_StormTech MC-3500 d +Cap (ADS StormTech® MC-3500 d rev 03/14 with Cap volume)

Effective Size= 70.4"W x 45.0"H => 15.33 sf x 7.17'L = 110.0 cf

Overall Size= 77.0"W x 45.0"H x 7.50'L with 0.33' Overlap

Cap Storage= 14.9 cf x 2 x 5 rows = 149.0 cf

77.0" Wide + 9.0" Spacing = 86.0" C-C Row Spacing

19 Chambers/Row x 7.17' Long +1.85' Cap Length x 2 = 139.93' Row Length +12.0" End Stone x 2 = 141.93' Base Length

5 Rows x 77.0" Wide + 9.0" Spacing x 4 + 12.0" Side Stone x 2 = 37.08' Base Width

9.0" Stone Base + 45.0" Chamber Height + 12.0" Stone Cover = 5.50' Field Height

95 Chambers x 110.0 cf + 14.9 cf Cap Volume x 2 x 5 Rows = 10,594.4 cf Chamber Storage

28,947.8 cf Field - 10,594.4 cf Chambers = 18,353.4 cf Stone x 40.0% Voids = 7,341.3 cf Stone Storage

Chamber Storage + Stone Storage = 17,935.8 cf = 0.412 af


Overall Storage Efficiency = 62.0%

Overall System Size = 141.93' x 37.08' x 5.50'

95 Chambers


1,072.1 cy Field

679.8 cy Stone



Pond Basin 1: (new Pond)

Hydrograph



Summary for Pond Basin 2: (new Pond)

Inflow Area = 0.693 ac, 38.96% Impervious, Inflow Depth = 0.48" for WQ event
 Inflow = 0.85 cfs @ 1.03 hrs, Volume= 0.028 af
 Outflow = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af, Atten= 100%, Lag= 0.0 min
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0.000 af
 Routed to Reach DP1-P : (new Reach)

Routing by Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs
 Peak Elev= 15.38' @ 2.45 hrs Surf.Area= 0.031 ac Storage= 0.028 af

Plug-Flow detention time= (not calculated: initial storage exceeds outflow)
 Center-of-Mass det. time= (not calculated: no outflow)

Volume	Invert	Avail.Storage	Storage Description
#1A	14.00'	0.029 af	34.75'W x 39.22'L x 3.50'H Field A 0.109 af Overall - 0.037 af Embedded = 0.073 af x 40.0% Voids
#2A	14.50'	0.037 af	ADS StormTech SC-740 +Cap x 35 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 35 Chambers in 7 Rows
		0.066 af	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	15.40'	2.5" Vert. Orifice/Grate C= 0.600 Limited to weir flow at low heads
#2	Primary	16.30'	6.0" Vert. Orifice/Grate X 2.00 C= 0.600 Limited to weir flow at low heads
#3	Primary	17.05'	3.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=14.00' (Free Discharge)

- 1=Orifice/Grate (Controls 0.00 cfs)
- 2=Orifice/Grate (Controls 0.00 cfs)
- 3=Sharp-Crested Rectangular Weir (Controls 0.00 cfs)

Pond Basin 2: (new Pond) - Chamber Wizard Field A**Chamber Model = ADS_StormTech SC-740 +Cap (ADS StormTech® SC-740 with cap length)**

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

5 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 37.22' Row Length +12.0" End Stone x 2 = 39.22' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

6.0" Stone Base + 30.0" Chamber Height + 6.0" Stone Cover = 3.50' Field Height

35 Chambers x 45.9 cf = 1,607.9 cf Chamber Storage

4,769.7 cf Field - 1,607.9 cf Chambers = 3,161.8 cf Stone x 40.0% Voids = 1,264.7 cf Stone Storage

Chamber Storage + Stone Storage = 2,872.6 cf = 0.066 af


Overall Storage Efficiency = 60.2%


Overall System Size = 39.22' x 34.75' x 3.50'

35 Chambers

176.7 cy Field

117.1 cy Stone



Pond Basin 2: (new Pond)**Hydrograph**

Appendix B

Recharge Worksheet

Annual Groundwater Recharge Analysis (based on GSR-32)

Select Township ↓

ESSEX CO., WEST ORANGE TOWN

Average Annual P (in)

49.0

Climatic Factor

1.67

Project Name:

Waymaker

Description:

Proposed Site Improvements

Analysis Date:

10/17/24

Pre-Developed Conditions

Land Segment	Area (acres)	TR-55 Land Cover	Soil	Annual Recharge (in)	Annual Recharge (cu.ft)
1	0.319	Impervious areas	Boonton	0.0	-
2	2.773	Open space	Boonton	14.9	150,467
3					
4					
5					
6					
7					
8	0				
9	0				
10	0				
11	0				
12	0				
13	0				
14	0				
15	0				
Total =	3.1			Total Annual Recharge (in)	Total Annual Recharge (cu-ft)
				13.4	150,467

Post-Developed Conditions

Land Segment	Area (acres)	TR-55 Land Cover	Soil	Annual Recharge (in)	Annual Recharge (cu.ft)
1	1.167	Impervious areas	Boonton	0.0	-
2	1.451	Open space	Boonton	14.9	78,734
3	0.474	Gravel, dirt	Boonton	6.9	11,787
4					
5	0				
6	0				
7	0				
8	0				
9	0				
10	0				
11	0				
12	0				
13	0				
14	0				
15	0				
Total =	3.1			Total Annual Recharge (in)	Total Annual Recharge (cu.ft)
				8.1	90,520

Annual Recharge Requirements Calculation ↓

% of Pre-Developed Annual Recharge to Preserve =	100%	Total Impervious Area (sq.ft)	50,835
Post-Development Annual Recharge Deficit=	59,947	(cubic feet)	
Recharge Efficiency Parameters Calculations (area averages)			
RWC=	3.50	(in)	DRWC= 0.00 (in)
ERWC =	0.58	(in)	EDRWC= 0.00 (in)

Procedure to fill the Pre-Development and Post-Development Conditions Tables

For each land segment, first enter the area, then select TR-55 Land Cover, then select Soil. Start from the top of the table and proceed downward. Don't leave blank rows (with A=0) in between your segment entries. Rows with A=0 will not be displayed or used in calculations. For impervious areas outside of standard lots select "Impervious Areas" as the Land Cover. Soil type for impervious areas are only required if an infiltration facility will be built within these areas.


This document was created by an application that isn't licensed to use novaPDF. Purchase a license to generate PDF files without this notice.

Project Name		Description		Analysis Date		BMP or LID Type					
Waymaker		Proposed Site Improvements		10/17/24		Subsurface Infiltration Basin 1					
Recharge BMP Input Parameters				Root Zone Water capacity Calculated Parameters				Recharge Design Parameters			
Parameter	Symbol	Value	Unit	Parameter	Symbol	Value	Unit	Parameter	Symbol	Value	Unit
BMP Area	ABMP	5263.0	sq.ft	Empty Portion of RWC under Post-D Natural Recharge	ERWC	0.61	in	Inches of Runoff to capture	Qdesign	0.30	in
BMP Effective Depth, this is the design variable Upper level of the BMP surface (negative if above ground)	dBMP	3.6	in	ERWC Modified to consider dEXC	EDRWC	0.00	in	Inches of Rainfall to capture	Pdesign	0.39	in
	dBMPu	108.0	in	Empty Portion of RWC under Infiltr. BMP	RERWC	0.00	in	Recharge Provided Avg. over Imp. Area		17.4	in
Depth of lower surface of BMP, must be >= dBMPu	dEXC	117.0	in					Runoff Captured Avg. over imp. Area		17.4	in
Post-development Land Segment Location of BMP , Input Zero if Location is distributed or undetermined	SegBMP	2	unitless								
				BMP Calculated Size Parameters				CALCULATION CHECK MESSAGES			
				ABMP/Aimp	Aratio	0.46	unitless	Volume Balance--> Solve Problem to satisfy Annual Recharge dBMP Check---> OK dEXC Check---> OK BMP Location---> OK			
				BMP Volume	VBMP	1,579	cu.ft				
Parameters from Annual Recharge Worksheet				System Performance Calculated Parameters							
Post-D Deficit Recharge (or desired recharge volume)	Vdef	7,121	cu.ft	Annual BMP Recharge Volume		63,423	cu.ft	OTHER NOTES Pdesign is accurate only after BMP dimensions are updated to make rech volume= deficit volume. The portion of BMP infiltration prior to filling and the area occupied by BMP are ignored in these calculations. Results are sensitive to dBMP, make sure dBMP selected is small enough for BMP to empty in less than 3 days. For land Segment Location of BMP if you select "impervious areas" RWC will be minimal but not zero as determined by the soil type and a shallow root zone for this Land Cover allowing consideration of lateral flow and other losses.			
Post-D Impervious Area (or target Impervious Area)	Aimp	11,326	sq.ft	Avg BMP Recharge Efficiency		100.0%	Represents % Infiltration Recharged				
Root Zone Water Capacity	RWC	3.69	in	%Rainfall became Runoff		78.5%	%				
RWC Modified to consider dEXC	DRWC	0.00	in	%Runoff Infiltrated		174.7%	%				
Climatic Factor	C-factor	1.67	no units	%Runoff Recharged		38.9%	%				
Average Annual P	Pavg	49.0	in	%Rainfall Recharged		30.6%	%				
Recharge Requirement over Imp. Area	dr	1.7	in								
How to solve for different recharge volumes: By default the spreadsheet assigns the values of total deficit recharge volume "Vdef" and total proposed impervious area "Aimp" from the "Annual Recharge" sheet to "Vdef" and "Aimp" on this page. This allows solution for a single BMP to handle the entire recharge requirement assuming the runoff from entire impervious area is available to the BMP. To solve for a smaller BMP or a LID-IMP to recharge only part of the recharge requirement, set Vdef to your target value and Aimp to impervious area directly connected to your infiltration facility and then solve for ABMP or dBMP. To go back to the default configuration click the "Default Vdef & Aimp" button.											

Project Name		Description		Analysis Date		BMP or LID Type					
Waymaker		Proposed Site Improvements		10/17/24		Subsurface Infiltration Basin 2					
Recharge BMP Input Parameters				Root Zone Water capacity Calculated Parameters				Recharge Design Parameters			
Parameter	Symbol	Value	Unit	Parameter	Symbol	Value	Unit	Parameter	Symbol	Value	Unit
BMP Area	ABMP	1363.0	sq.ft	Empty Portion of RWC under Post-D Natural Recharge	ERWC	0.61	in	Inches of Runoff to capture	Qdesign	0.30	in
BMP Effective Depth, this is the design variable Upper level of the BMP surface (negative if above ground)	dBMP	2.4	in	ERWC Modified to consider dEXC	EDRWC	0.00	in	Inches of Rainfall to capture	Pdesign	0.39	in
	dBMPu	60.0	in	Empty Portion of RWC under Infiltr. BMP	RERWC	0.00	in	Recharge Provided Avg. over Imp. Area		17.4	in
Depth of lower surface of BMP, must be >= dBMPu	dEXC	66.0	in					Runoff Captured Avg. over imp. Area		17.4	in
Post-development Land Segment Location of BMP , Input Zero if Location is distributed or undetermined	SegBMP	2	unitless								
				BMP Calculated Size Parameters				CALCULATION CHECK MESSAGES			
				ABMP/Aimp	Aratio	0.12	unitless	Volume Balance--> Solve Problem to satisfy Annual Recharge dBMP Check---> OK dEXC Check---> OK BMP Location---> OK			
				BMP Volume	VBMP	273	cu.ft				
Parameters from Annual Recharge Worksheet				System Performance Calculated Parameters				OTHER NOTES Pdesign is accurate only after BMP dimensions are updated to make rech volume= deficit volume. The portion of BMP infiltration prior to filling and the area occupied by BMP are ignored in these calculations. Results are sensitive to dBMP, make sure dBMP selected is small enough for BMP to empty in less than 3 days. For land Segment Location of BMP if you select "impervious areas" RWC will be minimal but not zero as determined by the soil type and a shallow root zone for this Land Cover allowing consideration of lateral flow and other losses.			
Post-D Deficit Recharge (or desired recharge volume)	Vdef	7,121	cu.ft	Annual BMP Recharge Volume		16,425	cu.ft				
Post-D Impervious Area (or target Impervious Area)	Aimp	11,326	sq.ft	Avg BMP Recharge Efficiency		100.0%	Represents % Infiltration Recharged				
Root Zone Water Capacity	RWC	3.69	in	%Rainfall became Runoff		78.5%	%				
RWC Modified to consider dEXC	DRWC	0.00	in	%Runoff Infiltrated		45.2%	%				
Climatic Factor	C-factor	1.67	no units	%Runoff Recharged		10.1%	%				
Average Annual P	Pavg	49.0	in	%Rainfall Recharged		7.9%	%				
Recharge Requirement over Imp. Area	dr	1.7	in								
How to solve for different recharge volumes: By default the spreadsheet assigns the values of total deficit recharge volume "Vdef" and total proposed impervious area "Aimp" from the "Annual Recharge" sheet to "Vdef" and "Aimp" on this page. This allows solution for a single BMP to handle the entire recharge requirement assuming the runoff from entire impervious area is available to the BMP. To solve for a smaller BMP or a LID-IMP to recharge only part of the recharge requirement, set Vdef to your target value and Aimp to impervious area directly connected to your infiltration facility and then solve for ABMP or dBMP. To go back to the default configuration click the "Default Vdef & Aimp" button.											

Appendix C

Existing and Proposed Drainage Area Map




Appendix D

USGS

HUC-11

Soil Survey Location Map

Hydrologic Soil Group—Essex County, New Jersey



Map Scale: 1:4,390 if printed on A portrait (8.5" x 11") sheet.

0 50 100 200 300 Meters

0 200 400 800 1200 Feet

Map projection: Web Mercator Corner coordinates: WGS84 Edge tics: UTM Zone 18N WGS84



Natural Resources
Conservation Service

Web Soil Survey
National Cooperative Soil Survey

6/28/2024
Page 1 of 4

MAP LEGEND

Area of Interest (AOI)

 Area of Interest (AOI)

Soils

Soil Rating Polygons

 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Lines

 A
 A/D
 B
 B/D
 C
 C/D
 D
 Not rated or not available

Soil Rating Points

 A
 A/D
 B
 B/D

 C
 C/D
 D
 Not rated or not available

Water Features

 Streams and Canals

Transportation

 Rails
 Interstate Highways
 US Routes
 Major Roads
 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Essex County, New Jersey
 Survey Area Data: Version 19, Aug 29, 2023

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Oct 10, 2022—Oct 16, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
BooBc	Boonton silt loam, red sandstone lowland, 0 to 8 percent slopes, extremely stony	C	7.7	8.1%
BooCc	Boonton silt loam, red sandstone lowland, 8 to 15 percent slopes, extremely stony	C	11.0	11.6%
BouB	Boonton - Urban land, Boonton substratum complex, 0 to 8 percent slopes	C	4.3	4.5%
BowrB	Boonton - Urban land, Boonton substratum complex, red sandstone lowland, 0 to 8 percent slopes	C	5.2	5.5%
BowrC	Boonton - Urban land, Boonton substratum complex, red sandstone lowland, 8 to 15 percent slopes	C	6.8	7.2%
HokCh	Holyoke silt loam, 0 to 15 percent slopes, very rocky	D	3.4	3.6%
RNAAC	Rock outcrop		3.9	4.2%
USBONB	Urban land, Boonton substratum - Boonton complex, 0 to 8 percent slopes		11.7	12.4%
YamnBc	Yalesville loam, 0 to 8 percent slopes, extremely stony	C	22.5	23.9%
YamnCc	Yalesville loam, 8 to 15 percent slopes, extremely stony	C	7.5	8.0%
YaohEh	Yalesville - Holyoke complex, 35 to 60 percent slopes, very rocky	C	10.4	11.0%
Totals for Area of Interest			94.3	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

Appendix E - Not Included in this Submission

Low Impact Development

Appendix F - Not Included in this Submission

Stormwater Conveyance System



Engineering & Design

Colliers Engineering & Design is a trusted provider of multi-discipline engineering, design and consulting services providing customized solutions for public and private clients through a network of offices nationwide.

For a full listing of our office locations, please visit colliersengineering.com

1 877 627 3772



*Civil/Site • Traffic/Transportation • Governmental • Survey/Geospatial
Infrastructure • Geotechnical/Environmental • Telecommunications • Utilities/Energy*