
EXHIBIT “A”

Rapid Pump & Meter Service Co.



February 9, 2024

Mr. Joe Elifani
Township of West Orange
Dept. of Public Works
25 Lakeside Avenue
West Orange, NJ 07502

Reference: Dogwood Pump Station Upgrades - 2024

Dear Mr. Elifani

As per your request and our site inspection, Rapid Pump & Meter Service Co., Inc. is pleased to offer the following **Budgetary** proposal for your approval.

The scope of work shall be as follows:

1. Furnish the labor, material and equipment required to remove existing eight-foot (8') concrete cover to access existing pipe and remove at wall penetration to install a bypass pump to maintain the station operation during reconstruction.
2. Furnish the labor, material and equipment required to remove all electrical conduits, lights, outlets, motors, piping, tanks and supports from concrete vault.
3. Furnish the labor, materials and equipment required to install one (1) new Aluminum Frog-mouth Access Cover over Wet Well.
4. Furnish the labor, material and equipment required to install the following equipment in the Wet Well:
 - Two (2) New Myers WG50 Grinder Pumps
 - Discharge Bases
 - Stainless Steel Rails
 - Two (2) four-inch (4") Gate Valves and Check Valves
 - PVC Stilling Well and Transducer
 - Stainless Steel Float Bracket and Floats

Township of West Orange

February 9, 2024

Page Two

5. Furnish the labor, material and equipment required to install a one (1) new Duplex Pump Control panel on the pole adjacent to the pump station with the following:
 - Steel back panel and aluminum inner door
 - Incoming power block
 - Main circuit breaker
 - IEC starters
 - Control transformer
 - Control circuit fuse
 - Hand-off-auto selector switches
 - Run lights
 - Seal fail lights and relays
 - Pump rail from overload and over-temp pilot lights
 - 22 mm lights and switches
 - Alarm test switch
 - Alarm light
 - Required control relays
 - Terminal strip and ground lugs
 - UL Listed labeled 698A
 - Power on light
 - Intrinsically safe relays
 - Bulldog pump controller
6. Furnish the labor, materials and equipment required to run conduit and wire from the Pump Control Panel to the Pump Station.
7. Furnish the labor, materials and equipment required to form and pour concrete pad for new generator.
8. Furnish the labor, materials and equipment required to install one (1) new 50kW Diesel Generator.
9. Furnish the labor, materials and equipment required to install one (1) new 100amp Automatic Transfer Switch.
10. Furnish the labor, materials and equipment required to make necessary electrical connections.
11. Furnish the labor, material and equipment required to operate and test the station remove the temporary bypass pump and hoses set the parameters on the transducer and float elevations check alarms, operate multiple cycles on automatic.

Township of West Orange

February 9, 2024

Page Three

The cost for the above scope of work shall be \$250,950.00

- PLEASE NOTE:
1. Should additional work be required it will be invoiced separately.
 2. All work shall be performed in a workmanlike manor using quality materials.
 3. Diesel for to fill generator to be provided by others.

All work is quoted on a straight time basis. If overtime is required, this would be at additional cost. Sales taxes, licenses, permits and/or fees, if any, are not included in this proposal.

Terms: Net 30 Days

Quote valid for: 30 Days

Should you have any questions, please feel free to contact me. Thank you for giving us the opportunity to quote on this project.

SUBMITTED BY:

Richard R. Morosco

L.S. Date February 9, 2024

Richard Morosco

Project Manager

Rapid Pump & Meter Service Co., Inc.

ACCEPTED BY:

Susan McCartney

L.S. Date _____

Mayor

Title

FOR: **West Orange DPW**

TF/ (Dogwood PS Upgrades - 2024)