

312-24

Exhibit “a”



**BEN
SHAFFER
RECREATION**

Ben Shaffer Recreation
P.O. Box 844
Lake Hopatcong NJ 07849 US

Proposal

TERMS

Net 30

REP

Scott
Tumminello

DATE

10/24/2024

Proposal #

4380-1

BILL TO

West Orange Township
Accts. Payable Dept.
66 Main Street
West Orange NJ 07052

SHIP TO

West Orange Recreation
Degnan Park
West Orange NJ 07052

CONTACT

William Kehoe

NJCPA COOP BC-BID-24
35

As requested, we are pleased to quote the following BC-BID-24-35; using Co-op #11-BECCP

ITEM# / DESCRIPTION	VENDOR	QTY	RATE	AMOUNT
NG-1019.5ADA_CL-BCCPA ADA Series Bleachers Chain-link Guardrail (customized to make 1 C-36A-0802100C04 36" elev. 8 row x 21'-0" bleacher Net seating capacity 81 + 4 ADA seats	National Recreation Systems	2.00	\$22,103.86	\$44,207.72
DISCOUNT		1.00	(\$884.15)	(\$884.15)
FREIGHT Freight		1.00	\$2,950.00	\$2,950.00
MHL Man-Hour Labor recieve/unload/build on existing asphalt including ground sills, and trash removal	BSR	230.00	\$145.00	\$33,350.00



Ben Shaffer Recreation
P.O. Box 844
Lake Hopatcong NJ 07849 US

Proposal

TERMS	REP	DATE	Proposal #
Net 30	Scott Tumminello	10/24/2024	4380-1

BILL TO
West Orange Township
Accts. Payable Dept.
66 Main Street
West Orange NJ 07052

SHIP TO
West Orange Recreation
Degnan Park
West Orange NJ 07052

CONTACT
William Kehoe

NJCPA COOP BC-BID-24
35

As requested, we are pleased to quote the following BC-BID-24-35; using Co-op #11-BECCP

ITEM# / DESCRIPTION	VENDOR	QTY	RATE	AMOUNT
---------------------	--------	-----	------	--------

Degnan Bleachers

\$79,623.57

The above items are priced in accordance with BC-BID-24-35; using Co-op #11-BECCP

Approximate delivery time is 14-16 weeks after receipt of order. When placing your order, kindly advise whom the trucker should notify to schedule delivery. The trucker will make one contact and that person must inform any other parties to coordinate delivery

Please make your Purchase Order payable to "Ben Shaffer Recreation Inc."

Standard colors and finish are quoted unless noted. Final count is the responsibility of the contractor/purchaser. Note that assembly/installation is NOT provided. Sales Tax will be added if applicable.

Aluminum angle understructure with 8" Rise / 24" Run 36 inch elevation, 63 inch clear front walkway 2 x 10 anodized aluminum seat plank with poly end caps Double 2 x 10 mill finish aluminum foot plank with aluminum end caps 1 x 6 riser rows 1 - 7 and (2) 1 x 6 top row risers mill finish (1) 4'-6" wide vertical aisle with mid aisle handrail 1 set of entry stairs Chain link guardrail system (1) Switch Back ADA accessibility ramp + 4 Wheel chair spaces

**Economical mill finish foot plank and risers have been specified on this quote. NRS will not be responsible for discoloration or staining (dark black, brown, or white residue) resulting from unavoidable condensation that occurs during packing, transporting and storage, preceding and/or during installation. Removal of these stains or replacement of boards upon completion of installation is not part of this contract because stained mill finish boards meet all specified requirements. A clear anodized finish may be quoted at an additional cost to avoid potential discoloration or staining.



Ben Shaffer Recreation
P.O. Box 844
Lake Hopatcong NJ 07849 US

Proposal

TERMS

Net 30

REP

Scott
Tumminello

DATE

10/24/2024

Proposal #

4380-1

Scott Tumminello
Ben Shaffer Recreation Inc.
Vice President, CPSI
Scott@BenShaffer.com
P: 973-294-5970

If you agree to the terms set forth in this proposal, please fill out name, signature, and date to confirm approval:

Estimate Approved By _____

Signature _____

Date _____

P.O. Number _____

Trucker Contact _____ Trucker Phone _____

Ship To Address _____

Conditions of Installation

RE: _____

Installations of equipment are subject to the following conditions and/or exclusions. Unless otherwise specifically included in the accompanying quote, Ben Shaffer Recreation and its contracted installers are not responsible for the following. If non-included services are needed, additional charges will apply and be billed at the contract cost:

- Unforeseen obstructions (such as in sub-surface) resulting in delayed installation or additional removal fees (rock, pipes, old building or site debris, hidden borders, oversized footings or other items that may be discovered during the excavation and removal process)
- Accepting delivery and/or checking materials
- Storage/security of materials at jobsite
- Relocation or transport of materials to jobsite
- Site preparation (grading, drainage, etc.)
- Finish work to site area (borders, protective surfacing)
- Removal/ Disposal of existing equipment
- Off-site disposal of shipping materials (cardboard, crating, etc.). Shipping materials will be neatly stacked on site, or placed in an on-site dumpster provided by site owner/manager.
- Equipment not included as part of original project number
- Any permits or clearance by utility companies and/or local building departments if applicable • Site security for rubber safety surface installation provided by others.
- If there are no on-site provisions for disposition of excavated footing materials (i.e. soil, blacktop, rocks, etc.)

NOTE: You should contact your utility companies directly to clear the area for all utilities prior to ordering equipment. Any necessary changes in equipment or layout can then be done prior to start of construction. You must indicate that the mark-out is for survey only. Customer is responsible for locating any privately owned utilities. We cannot be responsible for any damage to water, gas or other utilities as a result of owner's failure to clear underground plans.

If finish work is being done by installer (borders, protective surfacing), direct access for delivery trucks must be provided.

If site is to be graded or leveled, this must be coordinated and approved by installer to ensure adequate anchorage for structure.

The owner shall hold Ben Shaffer Recreation harmless in the event of injury due to lack of, or insufficient, resilient surface.

Sharp objects (i.e., sports spikes, heeled shoes, etc.) will damage rubber surface and void surface warranties

Ben Shaffer Recreation and its sub-contractors are in no way responsible for any issues associated with product design, manufacturing defect, lack of resilient surfacing or maintenance thereof.

I have read, understood, and agree to the above conditions.

Signed: _____ Print Name: _____ Date: _____

Please sign/save and email to sales@benshaffer.com; or print and fax to 973-663-4615.